

Township 3 N., R. 37 E., W.M.

Chains N.88° 25 ' E., on a true line, S. Bdy. of Sec. 13.
 Descending N.E.base of mountain through partially dead-
 ened,windfallen timber and dense undergrowth; bears
 N.W.& S.E.

38.52 A point 300 ft. below the Sec. Cor. and the $\frac{1}{4}$ Sec. Cor.,
 a fir, 6 ins. diam., marked and witnessed as described
 by the Surveyor-General.

Thence I run
 N.89° 39' E., on a true line, S. Bdy. of Sec. 13.

63.00 Foot; North Fork of the Umatilla River, 50 lks. wide,
 flows N. 60° W., thence ascend along N. side of canyon
 through scattering timber and patches of undergrowth.

78.70 A point 400 ft. above the $\frac{1}{4}$ Sec. Cor. and the Cor. of
 Secs. 13 & 24.

Note; When, 5 days later, the line between Secs. 23 & 24
 was closed 1.28 chs., S.89° 54' W. of the Cor. of Secs.
 13 & 14, the temp. $\frac{1}{4}$ Sec. Cor.,N. Bdy. of Sec. 24 was
 shown to be within the limit of that originally estab-
 lished,therefore the latter stands for two Secs.

Land; mountainous.

Soil; gravelly and stony; 3rd & 4th rates.

Timber; pine,fir, tamarack and cottonwood.

Undergrowth; pine, fir, tamarack, spruce, alder, willow,
 cottonwood and bunchgrasses. Good pasturage.

Mountainous land, 78.70 chs.

July 27,1900

S. 89° 45' W., on a blank line, S. Bdy. of Sec. 14, at
 1.28 chains, the temporary closing Cor. of Secs. 23 &
 24, set this day; at 41.28 chs. set tempoary $\frac{1}{4}$ Sec. Cor.
 N. Bdy. of Sec. 23; at 41.30 chs., the $\frac{1}{4}$ Sec. Cor., S.
 Bdy. of Sec. 14, bears N. 10 lks. distant; at 82.33
 chs. fall 58 lks. S. of the Cor. of Secs. 14 and 15,
 which is a Basalt Stone,18 x 14 x 12 ins., marked and
 witnessed as described by the Surveyor -General, ex-
 cept that the N.W. witness tree, a fir, 30 ins. in
 diam., bearing N.66° W., is 1 ch, 95 lks. distant,in-