

Township 3 N., R. 37 E., W.M.

Chains	<p>Sec. Cor., marked $\frac{1}{4}$ on W. face, from which,</p> <p>A pine, 6 ins. diam., bears S. 10° E., 1 ch. 73 lks. dist. marked $\frac{1}{4}$ S. 36, B.T.</p> <p>A fir, 9 ins. diam., bears N. 45° W., 78 lks. dist., marked $\frac{1}{4}$ S. 35, B.T.</p> <p>43.50 Abrupt descent thru thick timber and dense undergrowth., hill bears N. 70° W. and S. 70° E.</p> <p>50.00 Steeper slope N.E.</p> <p>65.25 Rill, 2 lks. wide, runs N. 30° W.</p> <p>70.00 Rill, 2 lks. wide, runs N. 30° W.</p> <p>73.50 Foot of mountain and cross narrow, stony bottom; bears N.E. & S. 75° W.</p> <p>74.40 Buck Creek, 15 lks. wide, runs S.W., over stony, gravelly bottom; trail along stream crosses to S. bank.</p> <p>75.00 Ascend; hill bears N. 40° E and S. 40° W.</p> <p>80.00 A point 1100 ft. below the $\frac{1}{4}$ Sec. Cor. and set an iron-stone 15 X 10 X 5 ins., 10 ins. in ground, for Cor. of Secs. 25, 26, 35 and 36, marked with $\frac{1}{4}$ notch on S. & E. edges, from which</p> <p>A fir, 16 ins. diam., bears N. 45° E., 61 lks. dist. marked-T3N, R. 37E., S. 25, B.T.</p> <p>A fir, 10 ins. diam., bears S. 73$\frac{1}{2}$° E., 27 lks. dist. marked-T3N., R37E., S. 36, B.T.</p> <p>A fir, 9 ins. diam., bears S. 6$\frac{1}{4}$° W., 52 lks. dist., marked-T3N., R37E., S. 35, B.T.</p> <p>A fir, 40 ins. diam., bears N. 74° W., 46 lks. dist. marked T3N, R37E., S. 26, B.T.</p> <p>Land; mountainous.</p> <p>Soil; gravelly and stony; 3rd & 4th rates.</p> <p>Thickly timbered with pine, fir, tamarack and cottonwood</p> <p>60.00 chs.</p> <p>Densely overgrown with pine, fir, tamarack, alder, willow cottonwood, yew, huckleberry, thimbleberry, rosebriar, fern and pinegrass, 60.00 chs.</p> <p>First quarter good bunchgrass pasture land.</p> <p>Mountainous and densely overgrown land, 80.00 chs.</p>
--------	--