

Township 3 N., R.37 E.,W.M.

Chains	marked $\frac{1}{4}$ S.25,B.T.
42.50	Steep slope N.10°E.
50.00	Descend.
52.00	Ascend; hill bears N.W.& S.E.
56.25	Top of ridge point, course N., descend along steep hill- side; bears N.70° E and S.70° W.
59.25	Steeper descent;bears N.E. and S.W.
72.50	Hill bears N.10° E. and S.10° W.
76.55	Foot of hill.
76.70	Trail along creek; bears N. 25° E. and S.20° W.
78.13	Buck Creek,12 lks. wide, clear, pure water, runs S.20°W.
78.25	Ascend steep bank.
79.60	A point 400 ft. below the $\frac{1}{4}$ Sec. Cor. and the Cor. of Secs. 25, 26,35 and 36. Land; mountainous. Soil; sandy, gravelly loam and stone;3rd & 4th rates. Timber;pine,fir and tamarack. Undergrowth; pine, fir, tamarack, alder, willow,huckle- berry, thimbleberry, bunchgrass, pinegrass,fern and rosebriar. Good grazing land. Mountainous land, 79.60 chs. July 30, 1900.
	North, on Sec. Guide Meridian, between Secs. 25 & 26. Ascending steep mountain thru thick timber and under- growth.
.23	A yellow pine, 34 ins. diam.,,on line, I mark with 2 notches on N.& S. sides.
1.75	Ravine, 8 ft. deep, course S.E.
3.25	Thence thru scattering timber with thick growth of grass
17.50	Thence hill bears N.20°E. and S.20° W.
40.00	A point 800 ft. above the Sec. Cor. and set a trapstone 20 x 20 x 3 ins., 15 ins. in ground, on E. slope of grassy ridge, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face, fr from which, A pine, 36 ins. diam., over on W. slope of ridge, bears S. 61 $\frac{1}{4}$ ° W., 3 chs. 25 lks. dist., marked $\frac{1}{4}$ S.