

Township 3 N., R.37 E., W.M.

Chains	Mountainous or heavily timbered land, 70.69 chs.
	July 31, 1900
	North on Sec. Guide Meridian, between Secs. 23 & 24. Descending steep mountain through heavy timber and dense undergrowth; bears N.80° E. and S. 80° W.
6.00	Thence through scattering timber.
8.75	Ravine, course N.40° W., fine spring of pure, cold water just below line. Ascend along steep, grassy hillside; bears N.25° W. and S.25 ° E.
9.50	Leave dense undergrowth; steep, stony hill.
14.00	Patch of dense undergrowth, 1 ch. wide.
17.20	Top of narrow, stony ridge point-N.W.; steep descent; bears N.80° E. and S. 80° W.
17.50	Enter heavy timber and dense undergrowth.
24.00	Ravine, course N.W.; thence steep slope westward.
24.50	Scattering timber and undergrowth.
28.75	Ravine, course N.80° W., ascend steep, grassy hill; bears N.W. & S.E.
29.00	Leave timber; bears N.70° W. and S.70° E.
40.00	A point 300 ft. below the Sec. Cor. and set a Basalt Stone, 20 X 10 X 5 ins., 5 ins. in the ground(stake rock and place mound of stones firmly about Cor.) for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face, and raise a mound of stone, 2 ft. base, $1\frac{1}{2}$ ft. high, N.E. of Cor. - the most suitable place. Pits impracticable.
45.00	Top of long, barren ridge, bearing N.20° W. and S.20°E. Descend steep side of mountain; bears N.40° W. and S.40° East.
47.50	Enter scattering timber and undergrowth.
49.50	Steeper descent into canyon of the North Fork; through fallen timber and dense undergrowth of old burn; bears N. and S.
61.25	Enter live timber; hill bears N.20° E. and S.20° W.
68.00	Through scattering timber.
72.25	Steeper descent of bluff-irregular bearing N.70° E.
76.600	A point 900 ft. below the $\frac{1}{4}$ Sec. Cor. and intersect the