

Township 3 N., R.37 E., W.M.

Chains	of ridge.
13.75	Enter dense undergrowth and timber; bears E.&W.
17.50	Leave timber and undergrowth.
28.25	Point-N.W.; descend into canyon of S. Fork through timber and dense undergrowth; hill bears N.W. and S.E.
40.00	A point about level with the Sec. Cor. and set a Basalt Stone 15 x 10 x 5 ins., 10 ins. in the ground, for $\frac{1}{4}$ Sec. Cor. and marked $\frac{1}{4}$ on W. face, from which, A fir, 24 ins. diam., bears S.41° E., 40 lks.dist. marked $\frac{1}{4}$ S.27, B.T. A fir, 6 ins. diam., bears N.13° W., 27 lks. dist. marked $\frac{1}{4}$ S.28, B.T. Thence through timber, scattering undergrowth; steep slope N.E.
44.50	Steeper descent through timber and undergrowth.
52.50	Cross ridge-point, N.15° E.
56.25	Down point-N.
57.25	Fir thickets.
58.50	Steeper descent; bears N.80° E. and S.80° W. At this point I loose the sun.
	August 14, 1900
	August 15:
70.00	Foot of point; gradual descent of bench through heavy timber.
75.00	Down river bank.
76.00	Cross stony bottom.
77.00	Trail- old abandoned toll road-- bears N.70° E. and S.70° W.
78.00	South Fork of Umatilla river, 50 lks. wide, flows N.75° E. over stony bottom.
78.75	Ascend steep, bluffly hill.
80.00	A point 1000 ft. below the $\frac{1}{4}$ Sec. Cor. and set a Basalt Stone, 20 x 10 x 4 ins., 15 ins. in the ground, for Cor. of Secs. 21, 22, 27 and 28, marked with 2 notches on S. and 3 notches on E. edges, from which A pine, 22 ins. diam., bears N.51 $\frac{1}{2}$ ° E., 62 lks.dist.