

| Chains | |
|--------|--|
| | Ascending steep, stony hill through scattering timber and undergrowth; bears E.&W. |
| 2.00 | Trail, E.&W. |
| 2.50 | Steep, irregular slope S.80° E. |
| 7.50 | Up bluffs. |
| 21.75 | Ravine, course E. |
| 34.00 | A fir, 15 ins. diam., on line, I mark with 2 notches on N.& S. sides. |
| 38.00 | Top of poinr-E., steep descent into canyon of N.Fork thru heavy timber; bears N.W. and S.E. |
| 40.00 | A point 500 ft. above the Sec. Cor. and set a Basalt Stone, 20 x 12 x 4 ins., 15 ins. in the ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face, from which, A fir, 16 ins. diam., bears S.80°E., 25 lks. dist., marked $\frac{1}{4}$ S.22, B.T. A fir, 17 ins. diam., bears S.79° W., 18 lks. dist. marked $\frac{1}{4}$ S.21, B.T. |
| 41.00 | Down steep bluff through dense undergrowth. |
| 47.50 | Steeper descent; bears N.80° W. & S.80° E. |
| 55.85 | Bluffs; bears N.70° W. & S.70 ° E. |
| 56.25 | Foot; cross gravelly, alluvial bottom. |
| 59.50 | Leave timber and undergrowth; bears E.&W. |
| 60.75 | Down river bank. |
| 60.95 | The Umatilla, 40 lks. wide, strong current, flows S.80° W. over stony bed. |
| 61.35 | Ascend bluff bank. |
| 62.00 | Top of bank. |
| 62.15 | Middle of old grade-abandoned stage road to Boise city, bears N.80° W. and S.80° E.; continue ascent thru timber and undergrowth. |
| 65.55 | Stock trail; bears N.30° E. and S.30° W. |
| 69.25 | Fir thicket. |
| 70.50 | Leave thicket; thence along E. side of Ravine. |
| 73.00 | Enter dense undergrowth. |
| 75.25 | Ravine, course S.35° W.; steeper ascenr and bearing N. 70° E. and S. 70° W. |