

Township 3 N., R. 37 E., W.M.

Chains 28.30	Top of Spur-E.; descend through timber and dense undergrowth; bears N.70° W. and S.70° E.
32.95	Foot; dry bed of stream, 3 lks. wide, in Ravine; course E.; ascend steep hill; bears N.30° E. and S.30° W.
40.00	A point 50 ft. below the Sec. Cor. and set a Basalt Stone, 15 x 10 x 4 ins., 10 ins. in the ground, in patch of dense undergrowth in shallow Ravine, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face, from which, A fir, 12 ins. diam., bears S.8 $\frac{1}{2}$ ° E., 65 lks. dist., marked $\frac{1}{4}$ S.32, B.T. No tree in limit W. of line; I raise a mound of stone, 2 ft. base, 1 $\frac{1}{2}$ ft. high, S. of Cor.-the only practicable point. Pits impracticable.
56.50	Trail along ridge; bears N. 20° E. and S.20° W.
59.00	Summit of Divide between S, Fork of Umatilla river and "Bob-sled" branch W. Descend through undergrowth and scattering, deadened timber; irregular slope N.80° W.
80.00	A point 350 ft. above the $\frac{1}{4}$ Sec. Cor. and set a Basalt Stone, 15 x 12 x 3 ins., 10 ins. in the ground, for Cor. of Secs. 29, 30, 31 & 32, marked with 1 notch on S. and 5 notches on E. edges, from which, A fir, 17 ins. diam.; bears S.17 $\frac{1}{2}$ ° E., 3 ch. 20 lks. dist., marked T.3 N., R.37 E., S.32, B.T. (No trees in limit). A fir, 28 ins. diam.; bears S.7 $\frac{1}{2}$ ° W., 2 ch., 67 lks. dist., marked T.3 N., R.37 E., S.31, B.T. No trees accessible in remaining area. I raise a mound of stone, 2 ft. base, 1 $\frac{1}{2}$ ft. high, W. of Cor. Pits impracticable. Land; mountainous. Soil; stony; 3rd & 4th rates. Timber; pine, fir, tamarack and spruce. Undergrowth; pine, fir, tamarack, spruce, alder, willow, cascara, huckleberry, thimble and redberry, elk and pinegrasses, birch, serviceberry and bunchgrass. Good pasturage. Mountainous land, 80.00 chs. Aug. 10, 1900