

Township 3 N., R.37 E., W.M.

| Chains | |
|--------|---|
| 81.60 | Intersect W. Bdy. of Tp., 1 ch.40 lks. S. of the Cor. of Secs. 24 & 25, as determined by the remains of the mound, decayed post and marked stone described by the Surveyor-General and 5 lks. S. of the closing Cor. of Secs. 19 & 30, as determined by retracement, a Basalt Stone, 6 x 6 x 5 ins., above ground, marked and witnessed as described in the field notes returned to the Surveyor-General. |
| | Thence I run, S.89° 53' E., on a true line between Secs. 19 & 30. Ascending steep, grassy hill through widely scattering timber and dense undergrowth; bears N.& S. |
| 2.25 | Stock trail; bears N.&S. |
| 5.75 | Leave dense undergrowth. |
| 10.50 | Top of bare, stony ridge; N.& S.; descend into the "Bobsled" canyon; bears N.W.& S.E. |
| 11.00 | Enter heavy timber and undergrowth; bears N.&S. |
| 21.75 | Ravine, course N.30° W.; dense undergrowth. |
| 37.00 | Hill slopes N. 20° E. |
| 41.60 | A point 200 ft. below the closing Sec. Cor. and set a Basalt Stone, 15 x 12 x 10 ins., 10 ins. in the ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face, from which, A fir, 18 ins. diam., bears S. 19° W., 37 lks. dist., marked $\frac{1}{4}$ S.30, B.T. A pine, 14 ins. diam., bears N.3 $\frac{1}{2}$ °W., 39 lks. dist. marked $\frac{1}{4}$ S.19, B.T. |
| | Thence through scattering timber and undergrowth. |
| 46.50 | Foot of hill; over gravel bar. |
| 47.47 | The "Bobsled" branch of the Umatilla River, 8 lks. wide, runs N.20° W.; ascend steep hill through timber and undergrowth; bears N.&S. |
| 48.45 | Stock trail; bears N.10°W. and S.10° E. |
| 51.75 | Scattering timber and undergrowth. |
| 54.50 | Top of point-N.30° W.; thence continue ascent of irregular slope of large Ravine N. thru timber & undergrowth bearing N.70° E. and S. 70° W. |