

Subdivisional Lines, T. 3 S., R. 30 E.

Chains		Feet
	$\frac{1}{4}$ Sec. Cor.	
50.00	Wm. H. Robinson's house brs. S. 26° W.	
70.00	" " " " " S. 11° E.	
80.08	The Cor. to Sec. 29, 30, 31, & 32. Land; surface undulating, Soil; 2nd and 3rd rate & large part 1st rate, good grass, good farming land. Sec. 32 is nearly all good farming land.	
	<hr/>	
	W. on a random line between Sec. 30 & 31, Var. 21° 00' E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
83.55	Intersected W. Bdy. 102 lks. S. of Cor. to Sec. 30 & 31 from which Cor. I run, S. 89° 13' E. on a true line between Sec. 30 & 31, Var. 21° 45' E.	
43.75	Set Basalt stone 20 x 12 x 8 on W. side of spur. for $\frac{1}{4}$ Sec. Cor.	
77.00	Brook, course N.W.	
81.00	Wagon road, course S.E. & N.W. to timber	
83.55	The Cor. to Secs. 29, 30, 31 & 32. Land; surface, E $\frac{1}{2}$ mile undulating. W. $\frac{1}{2}$ mile rolling, Soil E. $\frac{1}{2}$ mile 1st & 2nd rate. W. $\frac{1}{2}$ mile 3rd & 2nd rate. Good grass. Good for farming.	
	<hr/>	
	N. between Sec. 29 & 30, Var. 21° 00' E	
40.00	Set Basalt stone 24 x 12 x 8 on plateau for $\frac{1}{4}$ Sec. Cor.	
60.50	Wagon road, Course N.E. & S.W. to timber	
80.00	Set Basalt stone 20 x 10 x 8 on plateau, and post in mound of stone for corner to Secs, 19, 20, 29 & 30. Land; surface undulating, Soil; 2nd and small part 3rd rate, good grass, good farm- ing land, also good for grazing.	