

Exterior Lines, T.3 S., R.31 E., W. M.
 As surveyed by George S. Pershin, U.S. Deputy Surveyor,
 Under Contract No. 304,
 Dated Sept. 19, 1878.

Chains		Feet
	<p>I begin at post, in mound of stone, the Cor. of Tps. 2 & 3 S., Rs. 30$\frac{1}{2}$ & 31 E. and with Burts Improved Solar Compass, I run S. along W. Bdy. of Sec. 6. Var. 21° E.</p>	
3.00	Road to sawmill & timber, S. 10° E. & N. 10° W.	
40.00	Set stone, 17 x 12 x 5 on N. descent of plain for $\frac{1}{4}$ Sec. Cor.	
75.00	Cabin, unfinished, brs. S. 75° W.	
80.00	" " " N. 40° W.	+150
	<p>Set stone, 16 x 10 x 5 on N. slope, in mound of stone, for Cor. to Secs. 1, 12, 6 & 7; dug pits & drove stake, as per instructions. Land; surface, plain sloping N. Soil; 1st & 2nd rate. Good grass, good farming land.</p>	
	<p>S. along W. Bdy. of Sec. 7. Var. 21° E.</p>	
35.00	Begin to descend.	+ 50
40.00	Set stone, 24 x 12 x 5 in mound of stone for $\frac{1}{4}$ Sec. Cor.	
50.00	House brs. S. 60° W.	
66.00	" " N. 58° W.	
80.00	<p>Set stone, 17 x 10 x 8 on W. slope for Cor. to Secs. 7, 18, 12 & 13; dug pits and drove stake & raised mounds of stone. Land; surface rolling. Soil; 1st, 2nd & 3rd rate. Good grass; the larger part, good farming land & is all claimed.</p>	
	Nov. 4, 1878.	
	<p>S. along W. Bdy. of Sec. 18. Var. 20° E.</p>	
19.50	<p>Road, S.E. & N.W. to timber, begin to ascend. Willow Spring Ranch house, where Capt. Sperry was attacked by Indians, is S.E. on this road, about 18.00 chs. dist.</p>	50