

Exterior Lines, T.3 S., R.31 E., W. M.

Chains		Feet
	S. along E. Bdy. of Sec. 12. Var. 24°30'E.	
8.00	Top of knoll.	50
26.00	Enter timber, E. & W.	200
27.00	Spring branch, course W.	
40.00	Set pine post on W. hillside, for $\frac{1}{4}$ Sec. Cor. A pine, 45 ins. diam., brs. N.36°W., 110 lks. dist. No other trees. Along W. mountain side.	
80.00	Set stone, 18 x 10 x 6, at foot of ridge, on E. side of creek, for Cor. to Secs. 12, 13, 7 & 18. A fir, 20 ins. diam., brs. N.71°E., 52 lks. dist. A fir, 7 ins. diam., brs. S.48°E., 69 lks. dist. A tamarack, 30 ins. diam., brs. S.45°W., 101 lks. dist. A fir, 10 ins. diam., brs. N.40°W., 86 lks. dist. Land; surface mountainous. Soil; 3rd & 2nd rate. Timber; good in places, pine, fir & tamarack. Good grass in open ground.	
	South on E. Bdy. of Sec. 13. Var. 22°E.	
7.50	Brook, 10 lks. wide, course N.10°W.	
28.00	" " " " " N.10°E.	
40.00	A fir, 4 ins. diam., brs. $\frac{1}{4}$ Sec. Cor. 28 lks. dist. A pine, 13 ins. diam., brs. S.56°E., 28 lks. dist. A tamarack, 10 ins. diam., brs. N.50°W., 7 lks. dist.	300
46.00	Leave timber, N.E. & S.W.	
65.00	Enter timber, E. & W.	
80.00	Set stone, 17 x 12 x 4, near summit of mountain for Cor. to Secs. 13, 24, 18 & 19, from which; A fir, 8 ins. diam., brs. N.54°E., 39 lks. dist. A pine, 7 ins. diam., brs. S.21°E., 64 lks. dist. A fir, 24 ins. diam., brs. S.24°W., 38 lks. dist., A pine, 12 ins. diam., brs. N.38°W., 53 lks. dist. Land; surface mountainous.	