

Exterior Lines, T.4 S., R.31 E., W. M.

Chains		Feet
	S.89°55' W. on old true line along N. Bdy. of Sec. 5. Var.19°30'E.	
19.72	Old $\frac{1}{4}$ Sec. Cor. in good repair.	
24.50	Wagon road, course N. & S.	
30.00	Summit of ridge, course N.E. & S.W.	150
40.00	Set basalt stone, 20 x 8 x 8 on N.W. slope for $\frac{1}{4}$ Sec. Cor. A fir, 20 ins. diam., brs. S.13°W., 37 lk. dist.	
61.70	Cor. to T.3 S.,Rs. 30 $\frac{1}{2}$ & 31 E. A pine, 24 ins. diam., brs. N.55°E., 190 lks. dist. A pine, 16 ins. diam., brs. S.11°E., 283 lks. dist. A pine, 12 ins. diam., brs. S.17°W., 196 lks. dist. A pine, 28 ins. diam., brs. N.55°W., 111 lks. dist.	
80.00	Set basalt stone, 14 x 10 x 8 on small plateau for Cor. to Secs. 5 & 6. A pine, 14 ins. diam., brs. S.14°E., 590 lks. dist. A pine, 5 ins. diam., brs. S.42°W., 127 lks. dist. Land; surface E.60 chs., mountainous- W.20 chs., rolling. Soil; 3rd & 2nd rate. Mostly heavy timber, pine, tamarack & fir. Some good farming land on W. $\frac{1}{2}$ mile.	-250
	W. on old line along N. Bdy. of Secs. 6. Var.21°15'E.	
21.90	Old $\frac{1}{4}$ Sec. Cor.	
36.00	Leave timber, course N. & S.	
40.00	Set basalt stone, 17 x 12 x 8 ins. in mound of stone, on S. slope for $\frac{1}{4}$ Sec. Cor.	
61.60	Old Sec. Cor. for 35 & 36, T.3 S.,R.30 $\frac{1}{2}$ E.	
73.30	Cor. to T.3 S.,Rs. 30 & 30 $\frac{1}{2}$ E.	
81.20	Cor. to Tps. 4 S.,Rs. 30 & 31 E. Land; surface very rolling. Soil; 3rd & 2nd rate. Some pine timber, good grass. Some good farming land. Oct.21, 1880.	-300