

Subdivisional Lines, T. 3 S., R. 31 E., W. M.

| Chains | | Feet |
|--------|--|------|
| | and 13, from which Cor. I run | |
| | S. 69°47' W. on true line bet. Secs. 12 & 13 Var. 22°E. | |
| .50 | Brook, 8 lks. wide, course N.W. | |
| 39.93 | Set basalt stone, 16 x 12 x 10 on E. side, near top of ridge, for $\frac{1}{4}$ Sec. Cor., from which, A fir, 6 ins. diam., brs. N.8°W., 34 lks. dist. A fir, 11 ins diam., brs. S.50°E., 33 lks. dist. | +500 |
| 42.00 | Road to Camas Prairie, course N. & S. | |
| 44.00 | On ridge, course N. & S. | + 50 |
| 79.86 | The Cor. to Secs. 11, 12, 13 & 14 Land; surface mountainous. Soil; part 3rd & part 2nd rate. Mostly heavy timber; pine, tamarack & fir. Willow & young timber underbrush. May 7, 1879. | -400 |
| | N. bet. Secs. 11 & 12. Var. 21°45'E. | |
| 12.50 | Spring branch, course N.W. | -250 |
| 14.00 | Leave timber, E. & W. | |
| 15.50 | Road to sawmill, E. & W. | |
| 27.00 | John H. Keeney's house, brs. S.57°W. | |
| 40.00 | Set stone, 16 x 12 x 12 on W. face of mountain, for $\frac{1}{4}$ Sec. Cor. | |
| 54.500 | John H. Keeney's house, brs. S.34°W. | |
| 56.00 | Summit of ridge, irregular. | +600 |
| 80.00 | Set basalt stone, 20 x 10 x 4 on N.W. slope, for Cor. to Secs. 1, 2, 11 & 12. Set stake and built mounds of stone around stone & stake, in lieu of pits. Land; surface mountainous. Soil; 3rd, 2nd & part 1st rate. Timber; good, pine, tamarack & fir. Good grass on prairie or open mountain side. | -300 |
| | E. on random line bet. Secs. 1 & 12. Var. 24°15'E. | |