

## Subdivisional Lines, T.3 S., R.31 E., W. M.

| Chains |  | Feet |
|--------|--|------|
|        | N. bet. Secs. 26 & 27.<br><br>Var. 21°E.   |      |
| 13.00  | Begin steep descent.   |      |
| 32.00  | Spring branch, course N.E.   | 350  |
| 40.00  | Set granite stone, 16 x 8 x 6 on E. mountain side for $\frac{1}{4}$ Sec. Cor.<br><br>A pine, 18 ins. diam., brs. N. 28°W., 28 lks. dist.<br>A fir, 10 ins. diam., brs. S. 72°E., 53 lks. dist.   |      |
| 80.00  | Set granite stone, 16 x 10 x 5 on E. mountainside for Cor. to Secs. 22, 23, 26 & 27, from which,<br><br>A pine, 22 ins. diam., brs. N. 74°E., 88 lks; dist.<br>A fir, 8 ins. diam., brs. S. 44°E., 71 lks. dist.<br>A pine, 20 ins. diam., brs. S. 22°W., 86 lks. dist.<br>A pine, 30 ins. diam., brs. N. 48°W., 14 lks. dist. |      |
|        | Land; surface mountainous.<br><br>Soil; 3rd rate.<br><br>Heavy timber; tamarack, fir & pine. Occasional patches of young timber underbrush.  |      |
|        | E. on random line bet. Secs. 23 & 26.<br><br>Var. 21°30'E.   |      |
| 40.00  | Set post for temp. $\frac{1}{4}$ Sec. Cor.   |      |
| 80.86  | Intersected N. & S. line, 70 lks. S. of Cor. to Secs. 23, 24, 25 & 26, from which Cor., I run<br><br>S. 89°30'W. on true line bet. Secs. 23 & 26.<br><br>Var. 25°30'E.   |      |
|        | Down W. side of mountain.  |      |
| 40.43  | Set granite stone, 16 x 9 x 6 on W. face of mountain for $\frac{1}{4}$ Sec. Cor.<br><br>A pine, 22 ins. diam., brs. N. 32°W., 18 lks. dist.<br>A pine, 6 ins. diam., brs. S. 14 lks. dist.   |      |
| 58.00  | Brook, 15 lks. wide, course N.   | 700  |
| 80.86  | The Cor. to Secs. 22, 23, 26 & 27.<br><br>Land; surface mountainous.<br><br>Soil; 3rd rate.<br><br>Heavy timber; pine, tamarack & fir. Some young pine, fir & tamarack underbrush.<br><br>May 3, 1879.   | 500  |