

## Subdivisional Lines, T.3 S., R.31 E., W. M.

| Chains |  | Feet |
|--------|--|------|
|        | <p>Secs. 2 &amp; 3, from which Cor., I run<br/>S.0°59'E. on true line bet. Secs. 2 &amp; 3.<br/>Var.22°00'E.</p>   |      |
| 39.52  | Set stone, 16 x 12 x 10 on N. slope for $\frac{1}{4}$ Sec. Cor.  |      |
| 79.52  | <p>The Cor. to Secs. 2, 3, 10 &amp; 11.<br/>Land; surface, N. slope of mountain.<br/>Soil; 1st, 2nd &amp; 3rd rates, most of it good farming land,<br/>excellent grass.</p> <p>Note:-<br/>There is a farm &amp; house on Sec. 3, N.E. <math>\frac{1}{4}</math>, not in sight from<br/>line. I did not hear name of owner.</p>  | +500 |
|        | <p>N. bet. Secs. 33 &amp; 34.<br/>Var.19°E.</p>  |      |
| 40.00  | <p>Set fir post for <math>\frac{1}{4}</math> Sec. Cor. on neatly level surface.<br/>A fir, 18 ins. diam., brs. E. 34 lks. dist.<br/>A fir, 7 ins. diam., brs. N.85°W., 61 lks. dist.</p>   | +180 |
| 73.50  | Spring branch, course W.   |      |
| 80.00  | <p>Set basalt stone, 17 x 8 x 7 on S. slope, in small open<br/>glade for Cor. to Secs. 27, 28, 33 &amp; 34.<br/>A pine, 24 ins. diam., brs. N.44°E., 201 lks. dist.<br/>A pine, 20 ins. diam., brs. S.28°E., 149 lks. dist.<br/>A pine, 13 ins. diam., brs. S.80°W., 125 lks. dist.<br/>No tree near in Sec.28.</p> <p>Land; surface mountainous.<br/>Soil; 3rd &amp; 2nd rates.<br/>Heavy timber; with occasional open glades, pine, tamarack<br/>and fir. Some young pine, fir &amp; tamarack underbrush.<br/>May 6, 1879.</p> | -150 |
|        | <p>E. on random line bet. Secs. 27 &amp; 34.<br/>Var.22°30'E.</p>  |      |
| 40.00  | Set post for temp; $\frac{1}{4}$ Sec. Cor.   |      |
| 79.36  | <p>Intersected N. &amp; S. line, 22 lks. S. of Cor. to Secs. 26, 27, 34<br/>34 &amp; 35, from which Cor., I run<br/>S.89°51'W. on true line bet. Secs. 27 &amp; 34.</p>  |      |