

Subdivisional Lines; T.3 S., R.31 E., W. M.

Chains		Feet
	N.89°43' W. on true line bet. Secs. 22 & 27. Var.21°30'E.	
35.00	Brook, 4 lks. wide, course N.E.	
39.84	Set granite stone; 20 x 12 x 10 on S.E. side of knoll, for ½ Sec. Cor. A pine, 48 ins. diam., brs. N:8°W., 103 lks. dist. A fir, 6 ins. diam., brs. S.58°E., 54 lks. dist.	
79.68	The Cor. to Secs. 21, 22, 27 & 28. Land; surface very much chopped and broken. Soil; 3rd rate. and rocky. Heavy timber; tamarack, pine & fir.	
	N. bet. Secs. 21 & 22. Var.21°E.	
28.50	Spring branch, course N.W.	
40.00	Set pine post, 4 ins. diam., 4 ft. long, on W. side of ridge, E. of spring branch for ½ Sec. Cor. A fir, 7 ins. diam., brs. S.58°E., 8 lks. dist. A tamarack, 9 ins. diam., brs. W. 10 lks. dist.	
43.50	Spring branch, course N.E.	
80.00	Set granite stone, 16 x 10 x 8 on E. side of ridge, for Cor. to Secs. 15, 16, 21 & 22. A willow, 8 ins. diam., brs. N.48°E., 26 lks. dist. A pine, 13 ins. diam., brs. S.44°E., 13 lks. dist. A pine, 24 ins. diam., brs. S.58°W., 42 lks. dist. A pine, 36 ins. diam., brs. N.30°W., 56 lks. dist. Land; surface mountainous. Soil; 2nd rate & 3rd rate: Good timber; pine, tamarack & fir. May 7, 1879.	-500
	E. on random line bet. Secs. 15 & 22. Var. 20°15'E.	
40.00	Set post for temp. ½ Sec. Cor:	
80.68	Intersected N. & S. line, 78 lks. N. of Cor. to Secs. 14, 15, 22 & 23, from which, I run	