

Subdivisional Lines, T.3 S., R.31 E., W. M.

Chains		Feet
	N.89°27' W. on true line bet. Secs. 15 & 22. Var.21°15'E.	
40.34	Set basalt stone, 18 x 14 x 10, on top of spur, for $\frac{1}{4}$ Sec. Cor. A fir, 20 ins. diam., brs. N.42°E., 95 lks. dist. No trees on S. side.	+350
55.50	Brook, 6 lks. wide, course N.E.	-500
80.68	The Cor. to Secs. 15, 16, 21 & 22. Land; surface mountainous. Soil; 2nd & 3rd rate. Heavy timber; pine, tamarack & fir.	+700
<hr/>		
	N. bet. Secs. 15 & 16. Var.20°15'E.	
3.00	Leave timber, course E. & W, down near summit of ridge.	
40.00	Set basalt stone, 14 x 12 x 6, on W. side, near top of ridge, for $\frac{1}{4}$ Sec. Cor.	
80.00	Set basalt stone, 18 x 14 x 6 on W. face of ridge, for Cor. to Secs. 9, 10, 15 & 16; drove stake & raised mounds of stone in lieu of pits. Land; surface mountainous. Soil; 2nd & 3rd rates. Good grass. Part good farming land.	-500
<hr/>		
	E. on random line bet. Secs. 10 & 15. Var.21°30'E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.20	Intersected N. & S. line, 48 lks. N. of Cor. to Secs. 10, 11, 14 & 15, from which Cor., I run, N.89°39' W. on true line bet. Secs. 10 & 15. Var.21°00'E.	
00.15	Brook, 28 lks. wide, course N.W.	
20.00	On ridge, course N. & S.	+400
32.00	Brook, 6 lks. wide, course N.	-350
40.10	Set granite stone, 14 x 10 x 5 on E. side of ridge, for $\frac{1}{4}$ Sec. Cor.	