

Exterior Lines Tp. 4 S., R. 32 E.

Chains		Feet
	E. on the N. Bdy. of Sec. 3, Var. 20° 00' E.	
12.50	Open natural meadow, course N.E. & S.W.	
14.00	Spring Branch, course S.W.	
17.00	Enter timber, course S.W. & N.E.	
40.00	Set basalt stone on 20 x 10 x 6 on level in . . swale for $\frac{1}{4}$ Sec. Cor. A Pine 6 in. diam. brs. N. 52° W. 56 lks. dist. " " 6 " " " S. 50° W. 9 lks. dist.	
80.00	Set basalt stone 18 x 12 x 7 on slight S. Slope in open glade for Cor. to Sec. 3, 4, 33 & 34. A Pine 8 in. diam. brs. N. 68° E. 48 lks. dist. A Fir. 5 in. diam. brs. S. 78 E. 48 lks dist. " " 6 " " " N. 76° W. 117 lks. dist.	
	Land; surface rolling. Soil; 2nd and 3rd rate, heavy Pine, Tamarack & Fir Timber with open glades & burns, good grass.	
	W. on the N. Bdy. of Sec. 4, Var. 20! 45' E.	
14.00	A Ravine opens S.	-150
40.00	Set Basalt stone 14 x 10 x 5 on level for $\frac{1}{4}$ Sec. Cor. in open glade. A Pine 14 in. diam brs. N. 80° E. 141 lks dist. No trees S.	
80.00	Set basalt stone 16 x 10 x 4 on level for Cor. to Secs, . 4, 5, 32 and 33. A Tamarack 13 in. diam brs. N. 85° E. 20 lks dist. " " 4 in. diam. " S. 36° E. 25 lks. dist. " Pine 28 in. diam. brs. N. 39° W. 97 lks dist.	
	No trees. S.W. open glade. Land; surface rolling and broken, Soil; 2nd and 3rd rate, heavy Pine Tamarack & Fir timber with open glades, good grass.	