

## Exterior Lines Tp. 4 S., R. 32 E.

Chains		Feet
	and Fir and dense under brush. Pine, Tamarack & Fir.	
	N. between Sec. 24 and 19.	
		Var. 19° 00' E
12.75	A brook 12 lks. wide, course E. Descent about 300 ft.	
40.00	Set a basalt stone 10 x 8 x 8 ins. 7 ins. in ground on level on top of irregular hill for $\frac{1}{4}$ Sec. Cor. , marked $\frac{1}{4}$ on W. face. Ascend about 300 ft.	
	A Pine 5 ins. diam brs. N. 85) E. 16 lks. dist. Marked $\frac{1}{4}$ S. B.T.	
	A Pine 7 ins. diam. brs. S. 86° W. 29 lks dist. Marked $\frac{1}{4}$ S. B.T.	
68.00	Wagon Road to Springs course, N.E. & S.W.	
79.00	Same Road, course N.W. & S.E.	
80.00	Set a basalt stone 14 x 10 x 8 in. 10 ins. in ground on level for Cor. to Secs. 13, 24, 18 and 19. Marked with three notches on N. and S. edges from which, A Pine 10 ins. diam. brs. N. 38° E. 60 lks dist. Marked T. 3 S., R. 33 E., S. 18 B.T. A Pine 10 ins. diam. brs. S. 72° E. 43 lks. dist Marked T. 3 S., R. 33 E. S. 49 B.T. A Pine 6 ins. diam. brs. S. 28° W. 45 lks. dist. Marked T. 3 S., R. 32 E. S 24 B.T. A Pine 6 ins. diam. brs. N. 45° W. 31 lks. dist. Marked T. 3 S., R. 32 E. S. 13 B.T.	
	Land; surface, broken and partly mountainous. Soil; 3rd and 2nd rate, heavily timbered with Pine, Tamarack and Fir with underbrush. Pine, Tamarack and Fir, few open glades.	
	N. between Sec. 13 and 18,	
		Var. 24° 15' E
32.00	Enter large open glade, course E & W.	