

## Subdivisional Lines of T. 3 S., R. 32 E.

Chains.	Feet
<p>Land; surface mountainous. Soil; 3rd rate, heavily timbered with Pine, Tamarack and Fir. Some open glades. May 24, 1882</p>	
<p>W. bet. Sec. 17 and 20, Slightly descending, Var. 21° 30' E 40.00 Set a basalt stone 15 x 10 x 5 ins. 10 ins. in ground on S.W. slope in open glade for <math>\frac{1}{4}</math> Sec. Cor., marked <math>\frac{1}{4}</math> on N. face. A Pine 10 ins. diam. brs. N. 9° W. 211 lks. dist. Marked <math>\frac{1}{4}</math> S. B.T. A Tamarack 20 ins. diam. brs. S. 38° W. 90 lks. dist. Marked <math>\frac{1}{4}</math> S. B.T.</p>	
<p>55. 96 Intersected W. Bdy. 12.52 Chs. N. of Cor. to Secs. 13 and 24 of T. 3 S., R. 31 E. Set post 4 ft. long 5 ins. diam. 2 ft. in ground faced on N.E. and S.E. for Cor. to Sec. 17 and 20. Marked T. 3 S., S. 17 on N.E. and R. 32 E., S. 20 on S. E. A Pine 5 ins. diam. brs. N. 18° E. 29 lks. dist. Marked T. 3 S., R. 32 E., S. 17 B.T. A Tamarack 14 ins. diam. brs. S. 44° E. 30 lks. dist. Marked T. 3 S., R. 32 E., S. 20 B.T.</p>	
<p>Land; surface rolling, Soil; 3rd rate, heavily timbered with Pine, Tamarack and Fir and underbrush, same with some open glades.</p>	
<p>N. bet. Secs. 16 &amp; 17, Var. 21° 30' E. 10.50 Wagon road, N.W. and S.E., from settlement to timber, 12.50 Begin descending E. Side of bluff, 40.00 Set basalt stone 14 x 10 x 5 ins. 10 ins. in ground on steep E. slope for <math>\frac{1}{4}</math> Sec Cor., marked <math>\frac{1}{4}</math> on W. face. A Fir 16 ins. diam. brs. N. 80° E. 65 lks. dist.</p>	