

N. Bdy. T.4 S., R.33 E., W. M.

Chains		Feet
	S.89°50'E. on true line along N. Bdy. of Secs. 2. Over rolling ground. Var.20°30'E.	
40.00	Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on N. side, from which, A fir, 16 ins. diam., brs. N. 70 lks. dist., marked $\frac{1}{4}$ S., B.T. A pine, 18 ins. diam., brs. S.56°W., 14 lks. dist., marked $\frac{1}{4}$ S., B.T.	
80.00	Set basalt stone, 18 x 12 x 6 ins., 12 ins in ground, for Cor. to Secs. 1, 2, 35 & 36, marked with 1 notch on E. and 5 notches on W. edges, from which, A pine, 8 ins. diam., brs. N.70°E., 21 lks. dist., marked T.3 S., R.33 E., S.36, B.T. A pine, 8 ins. diam., brs. S.36°E., 39 lks. dist., marked T.4 S., R.33 E., S.1, B.T. A pine, 7 ins. diam., brs. S.47°W., 30 lks. dist., marked T.4 S., R.33 E., S.2, B.T. A pine, 9 ins. diam., brs. N.67°W., 60 lks. dist., marked T.3 S., R.33 E., S.35, B.T. Land; surface rolling. Soil; 3rd & 2nd rate. Heavy pine, tamarack & fir timber, with open glades, some dense thickets of young timber underbrush.	
	S.89°50'E. on true line on N. Bdy. Sec.1. Rolling ground. Var.20°15'E.	
40.00	Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on N. face, from which, A tamarack, 8 ins. diam., brs. N.46°W., 33 lks. dist., marked $\frac{1}{4}$ S., B.T. A fir, 7 ins. diam., brs. S.38°W., 9 lks. dist., marked $\frac{1}{4}$ S., B.T.	
47.75	A spring branch, course N. Descent 100 ft.	
80.00	Cor. to Tps. 3 & 4 S., Rs. 33 & 34 E.; Ascent 100 ft. Land; surface rolling. Soil; 2nd & 3rd rate. Pine, tamarack & fir timber, with open glades. Sept. 10, 1881.	