

Subdivisional Lines, T. 3 S., R. 33 E., W. M.

Chains		Feet
12.00	Enter bottom, brs. N.E. & S.W.	
14.65	Creek, 10 lks. wide, runs N.E., 200 ft. below Sec. Cor.	
15.50	Leave bottom, brs. N.E. Ascend along hillside.	
36.00	Begin to descend, hill brs. to N.W.	
40.00	Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on W. face, from which A tamarack, 20 ins. diam., brs. S. 37° W., 41 lks. dist., marked $\frac{1}{4}$ S., B.T. A tamarack, 20 ins. diam., brs. N. 87° E., 64 lks. dist., marked $\frac{1}{4}$ S., B.T.	
55.75	Brook, 5 lks. wide, runs E.	
80.00	Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Cor. to Secs. 22, 23, 26 & 27, marked, T. 3 S., S. 23 on N.E. R. 33 E., S. 22 on N.W. S. 27 on S.W. and S. 26 on S.E., with 2 notches on S. & E. edges, from which, A pine, 5 ins. diam., brs. N. 76° E., 26 lks. dist., marked T. 3 S., S. 23, B.T. A pine, 4 ins. diam., brs. S. 47° E., 26 lks. dist., marked S. 26, B.T. A pine, 5 ins. diam., brs. N. 23° W., marked — marked R. 33 E., S. 22, B.T. A pine, 12 ins. diam., brs. S. 76° W., 23 lks. dist., marked S. 27, B.T.	
	Land; mountainous.	
	Soil; 2nd rate.	
	Heavily timbered with pine, fir & tamarack.	
	Dense undergrowth of pine & fir.	
	Sept. 23, 1882.	
	N. bet. Secs. 22 & 23.	
	Var. 21° 30' E.	
.75	Brook, 3 lks. wide, runs S. 80° E. Ascend.	
27.50	Top of ridge, brs. N.E. & S.W. & descend 300 ft. above Sec. Cor.	