

Subdivisional Lines, T.2 S., R.33 E., W. M.

Chains		Feet
	Heavily timbered with pine, fir & tamarack. Dense undergrowth of pien, fir & tamarack.	
N. bet. Secs. 10 & 11		
	Descend.	Var. 20°E.
2.00	Spring branch, 4 lks. wide, runs N. 20°E.	
3.30	Same runs N.W.	
4.00	Ravine, course W. & ascend.	
38.00	Top of ridge, brs. N.W. & S.E., 600 ft. above Sec. Cor. & descend.	
40.00	Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on W. face, from which, A pine, 8 ins. diam., brs. S. 49°E., 35 lks. dist., marked $\frac{1}{4}$ S., B.T. A tamarack, 11 ins. diam., brs. N. 43°W., 35 lks. dist., marked $\frac{1}{4}$ S., B.T.	
80.00	Set basalt stone, 12 x 10 x 6 ins., 8 ins. in ground, for Cor. to Secs. 2, 3, 10 & 11, marked with 5 notches on S. and 2 on E. edges, from which, A pine, 6 ins. diam., brs. N. 66°E., 21 lks. dist., marked T.3 S., S.2, B.T. A pine, 22 ins. diam., brs. N. 57°W., 33 lks. dist., marked R.33 E., S. 3, B.T. A fir, 35 ins. diam., brs. S. 23°W., 52 lks. dist., marked S.10, B.T. A pine, 32 ins. diam., brs. S. 53°E., 101 lks. dist., marked S.11, B.T.	
	Land; mountainous.	
	Soil; 3rd rate.	
	Heavily timbered with pine, fir & tamarack. Undergrowth of pine, fir & tamarack.	
E. on random line bet. Secs. 2 & 11.		
	Descend.	Var. 19°30'E.
13.55	Spring branch, 5 lks. wide, runs N. Ascend 300 ft. below Sec. Cor.	