

Subdivisional Lines, T.3 S.,R.33 E.,W. M.

Chains		Feet
	<p>marked $\frac{1}{4}$ S.,B.T.</p> <p>Land; mountainous.</p> <p>Soil; 2nd rate.</p> <p>Heavily timbered with pine & fir.</p> <p>Dense pine & fir undergrowth.</p>	
	<p>N. bet. Secs. 27 & 28. Var.20°30'E,</p>	
15.00	Ravine, course S.E.	
40.00	<p>Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on W. face, from which,</p> <p>A pine, $3\frac{1}{2}$ ins. diam., brs. N.70°W., 9 lks. dist., marked $\frac{1}{4}$ S.,B.T.</p> <p>A pine, $3\frac{1}{2}$ ins. diam., brs. N.82°E., 10 lks. dist., marked $\frac{1}{4}$ S.,B.T.</p>	
68.25	Brook, 6 lks. wide, runs N.E. Ascend along hillside,	
80.00	<p>Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Cor. to Secs. 21, 22, 27 & 28, marked</p> <p>T.3 S.,S.22 on N.E.</p> <p>R.33 E.,S.21 on N.W.</p> <p>S.28 on S.W. and</p> <p>S.27 on S.E. with</p> <p>2 notches on S. and</p> <p>3 notches on E. edges, from which,</p> <p>A pine, 12 ins. diam., brs. N.52°E., 26 lks. dist., marked T.3 S.,S.22,B.T.</p> <p>A pine, 5 ins. diam., brs. N.37°W., 48 lks. dist., marked R.33 E.,S.21, B.T.</p> <p>A fir, 4 ins. diam., brs. S.62°W., 21 lks. dist., marked S.28,B.T.</p> <p>A pine, 5 ins. diam., brs. S.21°E., 42 lks. dist., marked S.27,B.T.</p> <p>Land; mountainous.</p> <p>Soil; 2nd rate.</p> <p>Heavily timbered with pine & fir.</p> <p>Dense undergrowth of pine & fir.</p>	