

Subdivisional Lines, T.3 S., R.33 E., W. M.

Chains

A pine, 8 ins. diam., brs. N.14°E., 33 lks. dist.,
marked T.3 S., R.33 E., S.33, B.T.

A pine, 10 ins. diam., brs. S.44°E., 15 lks. dist.,
marked T.4 S., R.33 E., S.4, B.T.

A fir, 8 ins. diam., brs. S.54°W., 14 lks. dist.,
marked T.4 S., R.33 E., S.5, B.T.

A fir, 10 ins. diam., brs. N.58°W., 56 lks. dist.,
marked T.3 S., R.33 E., S.32, B.T.

I run

N. bet. Secs. 32 & 33

Var. 22°E.

40.00 Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for
¼ Sec. Cor., marked ¼ S. on W. face, from which,

A pine, 8 ins. diam., brs. N.86°W., 52 lks. dist.,
marked ¼ S., B.T.

A pine, 3½ ins. diam., brs. S.18°E., 31 lks. dist.,
marked ¼ S., B.T.

80.00 Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for
Cor. to Secs. 28, 29, 32 & 33, marked

T.3 S., S.28 on N.E.

R.33 E., S.29 on N.W.

S.32 on S.W. and

S.33 on S.E., with

1 notch on S. and

4 notches on E. edges, from which

A tamarack, 18 ins. diam., brs. N.22°E., 37 lks. dist.,
marked T.3 S., S.28, B.T.

A tamarack, 3½ ins. diam., brs. N.39°W., 16 lks. dist.,
marked R.33 E., S.29, B.T.

A tamarack, 18 ins. diam., brs. S.48°W., 42 lks. dist.,
marked S.32, B.T.

A fir, 5 ins. diam., brs. S.57°E., 115 lks. dist.,
marked S.33, B.T.

Land; rolling.

Soil; 2nd rate.

Heavily timbered with pine & fir. Dense pine & fir undergrowth.