

## Subdivisional Lines, T.3 S., R.33 E., W. M.

Chains	
	<p>2 notches on S. and 4 notches on E. edges on hillside, slopes N.W., from which A tamarack, 4 ins. diam., brs. N.46°E., 38 lks. dist., marked T.33S.1, S.21, B.T. A pine, 3½ ins. diam., brs. N.46°W., 27 lks. dist., marked R.33 E., S.20, B.T. A tamarack, 5 ins. diam., brs. S.70°W., 30 lks. dist., marked S.29, B.T. A tamarack, 5 ins. diam., brs. S.8°E., 15 lks. dist., marked S.28, B.T.</p> <p>Land; rolling. Soil; 2nd rate. Heavily timbered with pine &amp; fir. Dense pine &amp; fir undergrowth.</p>
	<p>E. on random line bet. Secs. 21 &amp; 28 Ascend. Var. 21°E.</p> <p>12.00 Top of hill, brs. N.E. &amp; S.W. 40.00 Set temp. ¼ Sec. Cor. 60.00 Descend hill, brs. N. &amp; S. 79.90 Intersect N. &amp; S. line, 22 lks. N. of Cor. to Secs. 21, 22, 27 &amp; 28. Thence I run N.89°51' W. on true lien bet. Secs. 21 &amp; 28.</p> <p>39.95 Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for ¼ Sec. Cor., marked ¼ on N. face, from which A pine, 10 ins. diam., brs. S.5°E., 33 lks. dist., marked ¼ S., B.T. A pine, 10 ins. diam., brs. N.58°W., 23 lks. dist., marked ¼ S., B.T.</p> <p>79.90 The Cor. to Secs. 21, 20, 28 &amp; 29. Land; mountainous. Soil; 2nd rate. Heavily timbered with pine &amp; fir. Dense pine &amp; fir undergrowth.</p>