

Subdivisional Lines, T.3 S., R.33 E., W. M.

Chains	
	N. bet. Secs. 20 & 21. Var. 21° E. Descend to
18.50	Ravine, course W., 300 ft. below Sec. Cor., and ascend.
30.00	Top of ridge, brs. E. & W., 400 ft. above ravine and descend.
40.00	Set post in head of ravine, course N.W., 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on W. face, from which, A pine, 8 ins. diam., brs. S. 16° E., 28 lks. dist., marked $\frac{1}{4}$ S., B.T. A pine, 5 ins. diam., brs. S. 77° W., 30 lks. dist., marked $\frac{1}{4}$ S., B.T.
48.25	Ravine, course W., 200 ft. below $\frac{1}{4}$ Sec. Cor. Ascend steep hill.
52.00	Top of ridge, brs. E. & W., 300 ft. above last ravine & descend.
69.00	Ravine, course W., 500 ft. below top of ridge and ascend steep hill.
80.00	Set basalt stone, 14 x 12 x 6 ins., 8 ins. in ground, for Cor. to Secs. 16, 17, 20 & 21, marked with 3 notches on S. and 4 notches on E. edges, from which, A pine, 18 ins. diam., brs. N. 52° E., 150 lks. dist., marked T.3 S., S. 16, B.T. A pine, 15 ins. diam., brs. N. 30° W., 18 lks. dist., marked R.33 E., S. 17, B.T. A pine, 10 ins. diam., brs. S. 44° W., 31 lks. dist., marked S. 20, B.T. A pine, 18 ins. diam., brs. S. 59° E., 16 lks. dist., marked S. 21, B.T.
	Land; mountainous.
	Soil; 2nd & 3rd rate.
	Heavily timbered with pine & fir.
	Dense pine, fir & laurel undergrowth.
	<hr/> E. on random line bet. Secs. 16 & 21. Ascend. Var. 20° 15' E.