

Dependent Resurvey of 1st Standard Parallel N.
 -S. Bdy. of T. 5 N., R. 27 E.-
 by Otis O. Gould, Surveyor, under special
 instructions dated Sept. 9, 1940.

Chains

S.89.57'E., along the S. bdy. of sec. 36.

70.88 Proportionate measurement.

Set an iron post, 3 ft. long, 3 ins. diam., 27 ins. in the ground,
 with broken glass deposited at the base, for closing cor. to Tps.
 4 N., Rs. 27 and 28 E., with brass cap marked

T5N	R27E
S	S 36
S 1	S 6
R27E	R28E
T4N	
C	C
1941	

dig pits, 18x18x12 ins., E., S. and W. of post, 3 ft. dist.

80.30 Proportionate measurement.

Set an iron post, 3 ft. long, 3 ins. diam., 27 ins. in the ground,
 with broken glass deposited at the base, for standard cor. of
 Tps. 5 N., Rs. 27 and 28 E., with brass cap marked

S	C
T5N	
R27E	R28E
S36	S31
1941	

dig pits, 18x18x12 ins., N., E. and W. of post, 3 ft. dist.

Dependent Resurvey of East Bdy. of T. 4 N., R. 27 E.
 by Otis O. Gould, Surveyor, under special instructions
 dated Sept. 9, 1940.

"Reestablishment of the surveys executed by Ebenezer E. Haft,
 Deputy Surveyor, in 1860 and resurveyed by N. O. Walden, Deputy
 Surveyor, in 1874."

I commence the dependent resurvey of the E. bdy. at the cor. of
 Tps. 3 and 4 N., Rs. 27 and 28 E., which is a basalt stone,
 18x16x10 ins., set under surface of road, bearing N. and S., and
 marked with a cross (x).

Thence

N.0°07'W., on true line bet. secs. 31 and 36.

Over rolling land, along road.

1.15 House, bears W., about 1.00 ch. dist.

3.90 Barn, bears W., about 1.00 ch. dist.

25.90 House, bears E., about 1.50 chs. dist.

40.00 The $\frac{1}{2}$ sec. cor., which has been perpetuated with a basalt stone,
 16x10x8 ins., set under surface of roads, bearing N., S., and E.,
 and marked with a cross (x).