

Dependent Resurvey of East Bdy. of T. 4 N., R. 27 E.

Chains

At point for cor.

Set an iron post, 3 ft. long, 1 in. diam., 48 ins. in the ground,
1 ft. under surface of roads, with the basalt stone deposited at
the base, for $\frac{1}{4}$ sec. cor., with brass cap marked

$$\begin{array}{c} \frac{1}{4} \\ \uparrow \\ \text{S36} | \text{S31} \\ \hline 1941 \end{array}$$

At a point 30 lks. W. of true cor.

Set an iron post, 3 ft. long, 1 in. diam., 27 ins. in the ground,
with broken glass deposited at the base, for witness cor. to the
 $\frac{1}{4}$ sec. cor., with brass cap marked

$$\begin{array}{c} \frac{1}{4} \\ \uparrow \\ \text{S36} | \text{S31} \\ \hline 1941 \end{array} \quad \begin{array}{l} \text{WC} \\ 30 \\ \text{W} \end{array}$$

Thence

N.0°01'W., with new measurement,

21.35 Irrigation sitch, 8 lks. wide, course S.70°W.

40.14 The cor. of secs. 25, 30, 31, and 36, which has been perpetuated
with a basalt stone, 16x12x10 ins., firmly set on E. edge of
road, and marked with a cross (x).

At point for corner

Set an iron post, 3 ft. long, 2 ins. diam., 27 ins. in the ground,
with the basalt stone and glass deposited at the base, for cor.
of secs. 25, 30, 31, and 36, with brass cap marked

$$\begin{array}{c} \text{T4N} \\ \text{R27E} | \text{R28E} \\ \hline \text{S25} | \text{S30} \\ \hline \text{S36} | \text{S31} \\ \hline 1941 \end{array}$$

Land, rolling.

Soil, sandy, 2nd rate.

No timber; undergrowth, sagebrush and greasewood.

North bet. secs. 25 and 30.

Over rolling land, along E. edge of road.

23.00 Road, turns to the NW.

24.60 Irrigation canal, 30 lks. wide, course N.60°W.

37.80 Irrigation canal, 30 lks. wide, course N.30°E.

38.50 Old school house, bears W., about 5.00 chs. dist.

39.00 Road, bears N. and SW.; along road.

40.05 Proportionate measurement.