

Dependent Resurvey of East Bdy. of T. 4 N., R. 27 E.

Chains

at the base, for $\frac{1}{4}$ sec. cor., with brass cap marked

$$\begin{array}{c} \frac{1}{4} \\ \uparrow \\ \text{S13} | \text{S18} \\ \hline 1941 \end{array}$$

At a point 30 lks. E. of true cor.

Set an iron post, 3 ft. long, 1 in. diam., 27 ins. in the ground, with broken glass deposited at the base, for witness cor. to the $\frac{1}{4}$ sec. cor., with brass cap marked

$$\begin{array}{c} \frac{1}{4} \\ \uparrow \\ \text{WC} \\ 30 \text{ S13} | \text{S18} \\ \text{E} \\ \hline 1941 \end{array}$$

Thence

N.0°03'E., with new measurement.

- 0.10 Irrigation ditch, 6 lks. wide, course W.
- 8.60 Irrigation ditch, 8 lks. wide, course S.60°W.
- 15.00 House, bears W., about 4.00 chs. dist.
- 17.90 Irrigation ditch, 10 lks. wide, course S.70°W.
- 40.05 The cor. of secs. 7, 12, 13, and 18, determined in the exact center of cross roads, bears N., S., E., and W.

At point for cor.

Set an iron post, 3 ft. long, 2 ins. diam., 48 ins. in the ground, 1 ft. below surface of roads, with broken glass deposited at the base, for cor. of secs. 7, 12, 13, and 18, with brass cap marked

$$\begin{array}{c} \text{T4N} \\ \text{R27E} | \text{R28E} \\ \hline \text{S12} | \text{S 7} \\ \hline \text{S13} | \text{S18} \\ \hline 1941 \end{array}$$

At a point, N.45°E., 45 lks. dist. from true cor.

Set an iron post, 3 ft. long, 2 ins. diam., 27 ins. in the ground, with broken glass deposited at the base, for witness cor. to the cor. of secs. 7, 12, 13, and 18, with brass cap marked

$$\begin{array}{c} \text{T4N} \\ \text{T27E} | \text{R28E} \\ \text{WC} \text{ S12} | \text{S 7} \\ 45 \text{ S13} | \text{S18} \\ \hline \text{NE} \quad 1941 \end{array}$$

Land, rolling.
Soil, sandy, 2nd rate.
No timber; undergrowth, sagebrush and greasewood.

N.0°01'W., bet. secs. 7 and 12.

Over rolling land, along road.