

T. 4 N., R. 27 & 28 E., W.M.

Chains		Feet
80.00	Set post for Cor., to Secs., 12, 13, 18, & 7, in mound with trench and pits and deposited 1 pint of charcoal as per instructions. Soil; 3rd rate. Sandy, producing bunch grass. Land; level.	
<hr/> N. bet. Secs. 7 & 12 <div style="text-align: right;">Var. 20° E.</div>		
40.00	Set post for $\frac{1}{4}$ Sec., Cor., in mound with trench and pits, and deposited 1 pint of charcoal, as per instructions.	
80.00	Set post for Cor., to Secs. 6, 7, 1 & 12, in mound with trench and pits and deposited 1 pint of charcoal as per instructions. Soil; sandy, 3rd rate. Greasewood and bunch grass. Land; gently rolling.	
<hr/> N. bet. Secs. 1 and 6 <div style="text-align: right;">Var. 19° 50' E.</div>		
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench and pits, and deposited 1 pint of charcoal, as per instructions.	
80.47	Intersected 1st Standard parallel, N. 10.00 Chs., W. of Standard Cor., to Tps. 5 N., Rgs. 27 & 28 E., set post for Closing Cor. to Tps. 4 N., Rgs. 27 & 28 E., deposited 1 pt. charcoal and raised mound, with trench & pits, as per instructions. Land; rolling Soil; 3rd rate.	
<hr/> Resurvey of Exterior Bdy Lines of T. 4 N., R. 27 E., W.M. As surveyed by, Nicholas O. Walden, U.S. Deputy Surveyor Under Contract No. 209, Dated July 6, 1874.		
<hr/> Note:- The Cors. on the E. and W. Exterior Bdys. of this Tp., being obliterated, I am compelled to make a resurvey, of the same. (See note after line bet. Secs. 25 & 36, subdivision to T. 4 N., R. 27 E.) Accordingly I begin at the Cor. to T. 3 & 4 N., Rgs. 27 &		