

T. 4 N., R. 27 E., W.M. Oregon

Chains		Feet
	35 & 36. Drove Willow stakes, 2 ft. long, 2 ins. sq., in E. pit.	
40.00	W. on S. Bdy. of Sec. 35 The Standard $\frac{1}{4}$ Sec. Cor.	
	Dec. 3, 1874.	
	Subdivisional Lines of T. 4 N., R. 27 E., W.M. As surveyed by, Nicholas O. Walden, U.S. Deputy Surveyor. Under Contract No. 209 Dated July 6, 1874	
40.00	Begin at the established Cor. to Secs. 35 & 36, and run N. bet. Secs. 35 & 36	
80.00	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.	
	Drove charred stake and raised mound of earth with pits, etc., as per instructions, for Cor. to Secs. 25, 26, 35 & 36.	
	Drove Willow stake, 2 ft. long, 2 ins. sq., in S.E. pit. Land; gently rolling Soil; 2nd rate.	
40.00	E. on random line bet. Secs. 25 & 36 Set temp. $\frac{1}{4}$ Sec. Cor.	
79.70	Intersect E. Bdy. of Tp. 75 lks. S. of Cor. S. 89° 28' W. on true line	
39.85	Drove charred stake and raised mound of earth, with pits etc., as per instructions for $\frac{1}{4}$ Sec. Cor.	
79.70	The Cor. Land; gently rolling Soil; 2nd rate.	
	The above close is to my own Cor. as the E. Bdy. of T. 4 N., R. 27 E., was obliterated. I am compelled to resurvey T. See notes of resurvey of Exterior Bdys. of T. 4 N., R. 27 E.	
	Dec. 1, 1874.	