

Subdivisional Lines of T. 4 N., R. 27 E., W.M.

Chains		Feet
	Land; gently rolling Soil; 2nd rate.	
	<hr/>	
	E. on random line bet. Secs. 1 & 12	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.92	Intersected E. Bdy. of Tp., 49 lks. S. of Cor. S. $89^{\circ} 39'$ W. on true line	
39.96	Drove charred stakes and raised mound of earth, with pits & etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.	
79.92	The Cor. Land; gently rolling Soil; 2nd rate.	
	<hr/>	
	N. bet. Secs. 1 & 2	
		Var. $21^{\circ} 20'$ E.
40.00	Drove charred stake, and raised mound of earth, with pits etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.	
81.00	Intersect 1st Standard Parallel, 9.25 lks. W. of the Cor. to Secs. 35 & 36. Where I drove charred stake, and raised mound of earth, with pits and., as per instructions, for Closing Cor. to Secs. 1 and 2. Drove willow stake, 2 ft. long, 2 ins. sq., in E. pit.	
	Land: gently rolling Soil; 2nd rate. This close, is to my own Cor., as the Cor. to Secs. 35 & 36, on Standard line, had become obliterated. I am compelled to reestablish it. Also other portions of same line. See Resurvey of 1st Standard Parallel, N..	
		Dec. 3, 1874
	<hr/>	
	N. bet. Secs. 34 & 35	
40.00	Drove charred stake, and raised mound of earth with pits etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.	
80.00	Drove charred stake and raised mound of earth, with pits etc., as per instructions, for Cor. to Secs. 26, 27, 34 & 35.	