

## Subdivisional Lines of T. 4 N., R. 27 E., W.M.

| Chains |   | Feet |
|--------|---|------|
| 81.70  | <p>Intersect, 1st standard Parallel 960 lks. W. of the Standard Cor. to Secs. 34 &amp; 35, where:-</p> <p>Drove charred stake and raised mound of earth, with pits etc., as per instructions, for Closing Cor. to Secs. 2, &amp; 3.</p> <p>Drove willow stake, 2 ft. long, 2 ins. sq., in E. pit.</p> <p>Land; gently rolling</p> <p>Soil; 2nd rate.</p> <p style="text-align: right;">Dec. 4, 1874</p> |      |
|        | N. bet. Secs. 33 & 34   |      |
| 40.00  | Drove charred stake, and raised mound of earth, with pits etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.  |      |
| 80;00  | <p>Drove charred stake, and raised mound of earth with pits etc., as per instructions, for Cor. to Secs. 27, 28, 33 &amp; 34. Drove willow stake, 2 ft. long, 2 ins. sq., in S.E. pit.</p> <p>Land; gently rolling</p> <p>Soil; 2nd rate.</p>   |      |
|        | E. on random line bet. Sec. 27 & 34   |      |
| 40.00  | Set temp. $\frac{1}{4}$ Sec. Cor.   |      |
| 79.60  | <p>Intersect N. and S. line, at Cor.</p> <p>W. on true line</p>   |      |
| 39.80  | Drove charred stake, and raised mound of earth, with pits etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.  |      |
| 79.60  | <p>The Cor.</p> <p>Land; gently rolling</p> <p>Soil; 2nd rate.</p>  |      |
|        | N. bet. Secs. 27 & 28<br>Var. 21° 15' E.  |      |
| 40.00  | Drove charred stake and raised mound of earth with pits etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.  |      |
| 80.00  | Drove charred stake and raised mound of earth with pits etc., as per instructions for Cor. to Secs. 21, 22, 27  |      |