

Exterior Bdy. of T. 4 N., R. 29 E., W.M.  
 As surveyed by Wm. B. Campbell, U.S. Deputy Surveyor  
 Under Contract No. 95,  
 Dated September 19, 1860

Chains		Feet
	N. bet. Secs. 31 and 36	
		Var. 20° 30' E.
7.80	The Slough, no water at this season, 100 lks wide	E. & W.
15.35	To " " " " " " " " " " " "	" " " " " "
18.00	To " " " " " " " " " " " "	Running N. 10° E
33.90	To wagon road; course E. and W.	
40.00	Set a post for $\frac{1}{4}$ Sec. Cor., drove chard stake and raised mound of earth, with trench and pits, as per instructions.	
48.00	To dry slough, 100 lks. wide, course N.W. and S.E.	
59.50	To the Unatilla River, 164 lks. wide, course W., bank, 8 ft. high, offset E. 250 lks. and chained across river, and offset back 2.50 into line	
61.00	Enter Timber	
63.00	Leave " & ascend bluff	
80.00	Set a post for Cor. to Secs., 25, 30, 31 and 36, Drove a chard stake and raised a mound of earth with trench, pits, as per instructions.	
	Land; rolling, prairie	
	Soil; in river botton, 1st rate, on bluff 3 rd rate.	
	N. bet. Secs. 25 and 30	
		Var. 20° 15' E.
7.20	To a wagon road, running S.E. and N.W.	
12.00	To a trail, running S.E. and N.W.	
40.00	Set a post for $\frac{1}{4}$ Sec. Cor., drove a chard stake and raised a mound of earth with trench, pits, as per instructions.	
	A Big canon, through which the Columbia River passes	brs.
	N. 43° E., 12 or 13 miles distant.	
80.00	Set a post for Cor. to Secs. 25, 30, 19 & 24, drove a chard stake, raised a mound of earth with trench & pits, as per instructions.	
	Land; nearly level, prairie	
	Soil; 3rd rate.	
	N. bet. Secs. 19 & 24	
		Var. 19° 55' E.