

## Subdivisional Lines of T. 4 N., R. 28 E., W.M.

Chains		Feet
	35, 36, 25 & 26, brs. S., chained a base E., 54 lks., Cor. brs. S. 20° W., making distance 1.50 lks. to Witness Cor., hence it is 50 lks. N. to the true Cor. in the River. Soil; 1st rate. Timer, Balm, Maple and	
	<hr/>	
	N. bet. Secs. 25 & 26	
.50	Leave Umatilla, bearing W.	
1.50	Leave timber and enter prairie	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits and deposited 1 pint of charcoal as per instructions.	
80.00	Set post for Cor. to Secs. 23, 24, 25 & 26, in mound with trench and pits and deposited 1 pint charcoal as per instructions.	
	<hr/>	
	E. on a random line bet. Secs. 25 & 24 Var. 20° E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.90	Intersect E. Bdy. of tp., 87 lks. N. of the Cor. to Secs. 25, 24, 19 & 30, from which Cor. I run N. 89° 23' W. on true line bet. Secs. 24 & 25	
40.45	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits and deposited 1 pint of charcoal as per instructions.	
43.60	Road from Umatilla to Columbia, brs. N.W.	
80.90	The Cor. to Secs. 23, 24, 25 & 26 Soil; 2nd and 3rd rate. Land; gently rolling Timber, Balm	
	<hr/>	
	N. bet. Secs. 23 & 24	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits and deposited 1 pint of charcoal, as per instructions.	
71.00	Road from Umatilla to Columbia, brs. N.W.	
80.00	Set post for Cor. to Secs. 23, 24, 13 & 14, in mound with trench and pits and deposited 1 pint of charcoal as per instructions. Soil; 3rd rate, producing grass.	