

## Subdivisional Lines of T. 4 N., R. 28 E., W.M.

Chains		Feet
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits and deposited 1 pint of charcoal as per instructions.	
80.00	Set post for Cor. to Secs. 22, 23, 26 & 27, in mound with trench and pits and deposited 1 pint of charcoal, as per instructions. Soil; 1st and 2nd rate, Timber, Balm, Maple and Willow.	
<hr/>		
E. on random line bet. Sec. 23 & 26		
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	Var. 19° 55' E
79.93	Intersect N. and S. line 13 lks. N. of the Cor. to Secs. 23, 24, 25 & 26, from which Cor. I run N. 89° 54' W. on true line bet. Secs. 23 & 26	
39.96 $\frac{1}{2}$	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits and deposited 1 pint charcoal as per instructions.	
79.93	The cor. to Secs. 22, 23, 26 & 27 Soil; 3rd rate Land; rolling	
<hr/>		
N. bet. Secs. 22 & 23		
40.00	Set post for $\frac{1}{4}$ Sec. Cor. in mound with trenches and pits & deposited 1 pint of charcoal as per instructions	
80.00	Set post for Cor. to Secs. 14, 15, 22 & 23, in mound with trench and pits and deposited 1 pint of charcoal as per instructions. Soil; 2nd & 3rd rate, producing grass. Land; rolling	
<hr/>		
E. on random line bet . Secs. 14 & 23		
40.00	Set post for temp $\frac{1}{4}$ Sec. Cor.	Var. 20° E.
80.41	Intersect N. and S. line, 64 lks. N. of the Cor. to Secs. 13, 14, 23 & 24, from which Cor. I run N. 89° 33' W. on true line bet. Secs. 14 & 23	
5.60	Road from Umatilla to Columbia, brs. N.W.	
40.20 $\frac{1}{2}$	Set post for $\frac{1}{4}$ Sec. Cor. in mound with trench and pits, and deposited 1 pint of charcoal as per instructions.	
80.41	The Cor. to Secs. 14, 15, 22 & 23 Soil; 3rd rate Land; rolling	
Oct 20th 1860.		