

## Subdivisional Lines of T. 4 N., R. 28 E., W.M.

Chains		Feet
	Soil; 3rd rate, sandy Land; rolling, undergrowth, sage and greasewood.	
40.00	N. on random bet. Secs. 2 & 3 Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.83	Intersect N. Bdy. of Tp., 96 lks. W. of the Closing Cor. for Secs. 2 & 3, from which Cor. I run S. $0^{\circ} 41'$ W. on true line bet. Secs. 2 & 3	
42.83	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits and deposited 1 pint of charcoal as per instructions.	
82.83	The Cor. to Secs. 2, 3, 10 & 11  Soil; 3rd rate, sandy Land; rolling, thick undergrowth of wild sagewood.	
	N. bet. Sec. 33 & 34 Descend gradually	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits and deposited 1 pint of charcoal as per instructions.	
58.00	Enter thick undergrowth, willow etc.	
59.15	Intersect Umatilla, 1.00 chs. wide, runs, W.	
70.00	Leave undergrowth timber and low land, and ascend a rise of ground.	
80.00	Set post for Cor. to Secs. 27, 28, 33 & 34, in mound with trench and pits and deposited 1 pint charcoal as per instructions.	
	Soil; 2nd and 3rd rate. Timber, Ash, Maple, Willow, etc., undergrowth Willow, Haw. etc. etc. Oct. 21, 1860	
	E. on random line bet. Secs. 27 & 34 Oct. 22, 1860 Var. $19^{\circ} 40'$ E	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.02	Intersect N. and S. line, 10 lks. N. of the Cor. to Secs. 26, 27, 34 & 35, from which Cor. I run N. $89^{\circ} 56'$ W. on true line bet. Secs. 27 & 34	
7.10	Umatilla river, 140 chs. wide, brs. W., S.W.	
39.00	Enter swamp brs. N.E. and S.W.	
40.01	Set post for $\frac{1}{4}$ Sec. Cor., in swamp, from which A willow, 15 ins. diam. brs. N. $82^{\circ}$ E., 1.00 chs. A " 4 " " " S. $70^{\circ}$ E., 1.20 Chs.	
42.00	Leave swamp	