

Subdivisional Lines of T. 4 N., R. 28 E., W.M.

Chains		Feet
43.00	Leave undergrowth and timber and enter prairie	
80.02	The Cor. to Secs. 33, 34, ² 37 & 28 W. $\frac{1}{2}$ mile rolling land, 2nd rate, E. $\frac{1}{2}$ mile low wet ground, subject to overflow.	
<hr/>		
N. bet. Secs. 27 & 28		
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits and deposited 1 pint charcoal, as per instructions.	
80.00	Set post for Cor. to Secs. 21, 22, 27 & 28, in mound with trench and pits and deposited 1 pint charcoal as per instructions.	
<hr/>		
Soil; 3rd rate, producing grass. Land; rolling		
<hr/>		
E. on random line bet. Secs. 22 & 27		
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	Var. 19° 45' E.
80.08	Intersect N. and S. line, 6 lks. N. of the Cor. to Secs. 22, 23, 26 & 27, from which Cor. I run N. 89° 57' W. on true line bet. Secs. 22 & 27	
40.04	Set post for $\frac{1}{4}$ Sec. Cor. in mound with trench and pits and deposited 1 pint of charcoal, as per instructions.	
80.08	The Cor. to Secs. 21, 22, 27 & 28 Soil; 3rd rate, producing grass. Land; rolling.	
<hr/>		
N. bet. 21 & 22		
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits, and deposited 1 pint of charcoal, as per instructions.	
80.00	Set post for Cor. to Secs. 15, 16, 21 & 22, in mound with trench and pits and deposited 1 pint charcoal as per instructions.	
<hr/>		
Soil; 3rd rate, producing grass. Land; gently rolling.		
<hr/>		
E. on random line bet. Secs. 15 & 22		
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	Var. 19° 45' E.
79.70	Intersect N. and S. line, 18 lks. N. of the Cor. to Secs. 14, 15, 22 & 23, from which Cor. I run N. 89° 52' W. on true line bet. Secs. 15 & 22.	
39.85	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits & deposited 1 pint of charcoal, as per instructions.	