

Subdivisional Lines of T. 4 N., 28 E., W.M.

Chains		Feet
	the S. and Brs. S.	
56.00	A ledge of burnt stone, 10 ft. high	
79.52	The Cor. to Secs. 3, 4, 9 & 10 Soil; 3rd rate. Land; level, considerable growth of sagewood.	
<hr/>		
	N. on random line bet. Secs. 3 & 4	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
82.50	Intersect N. Bdy. of Tp., 30 lks. W. of the C. Cor. for Secs. 3 & 4, on 1st stand. parallel N., from which Cor. I run S. $0^{\circ} 13'$ W. on true line bet. Secs. 3 & 4	
42.50	Set post for $\frac{1}{4}$ sec. Cor., in mound with trench and pits and deposited 1 pint of charcoal as per instructions.	
48.00	Road leading to Columbia river, brs. N.W.	
82.50	The Cor. to Secs. 3, 4, 9 & 10. Soil; level on the S. and rolling on the N. part. Soil; 3rd rate, Sagewood.	
<hr/>		
	N. bet. Secs. 32 & 33	
35.00	Trail up Umatilla, brs. E. N.E.	
37.00	Butter Creek (dry) runs, N. N.E.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits & deposited 1 pint charcoal as per instructions.	
	Enter Umatilla bottom	
80.00	Set post for Cor., to Secs. 28, 29, 32 & 33, in mound with trench and pits and deposited 1 pint charcoal as per instructions. Soil; 2nd and 3rd rate. Land; descending gradually from Cor., to	
<hr/>		
	E. on random line bet. Secs. 28 & 33 Var. $19^{\circ} 50'$ E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.56	Intersect N. and S. line, 58 lks. N. of the Cor. to Secs. 27, 28, 33 & 34, from which Cor. I run N. $89^{\circ} 35'$ W. on true line bet. Secs. 28 & 33	
37.25	Umatilla river, 1.25 chs. wide, runs, W. N.W.	
40.28	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits and deposited 1 pint of charcoal as per instructions.	
80.56	The Cor. to Secs. 28, 29, 32 & 33. Land; level, 3rd rate.	