

Subdivisional Lines of T. 4 N., R. 28 E., W.M.

Chains		Feet
	Soil; sandy, 3rd rate, producing Sage and grass.	
	W. on random line bet. Secs. 19 & 30	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
76.54	Intersect W. Bdy. of Tp., 10 lks. S. of the Cor. to Secs. 24, 25, 19 & 30, from which Cor. I run	
	S. $89^{\circ} 56'$ E. on true line bet. Secs. 19 & 30	
36.54	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits and deposited 1 pint of charcoal, as per instructions.	
87.70	Intersect left bank of Umatilla, from opposite bank, flag brs. S. $89^{\circ} 56'$ E., ch. a base S., 82 lks., flag brs. N. $73\frac{1}{2}^{\circ}$ E., departure 269 lks.	
40.39	Right bank of Umatilla	
	Enter willow	
41.00	Leave "	
76.54	The Cor. to Secs. 19, 20, 29 & 30	
	Soil; 3rd rate.	
	Land; rolling, on the Umatilla bank, very large sagewood.	
	N. bet. Secs. 19 & 20	
4.00	Umatilla, 160 lks. wide, runs, E., N.E.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits, and deposited 1 pint of charcoal, as per instructions.	
80.00	Set post for Cor. to Secs. 17, 18, 19 & 20, in mound with trench and pits and deposited 1 pint of charcoal as per instructions.	
	Soil; 3rd rate and sandy, producing but little vegetation.	
	E. on random line bet. Secs. 17 & 20	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor. Var. 20° E.	
79.92	Intersect N. and S. line, 85 lks. N. of the Cor. to Secs. 16, 17, 20 & 21, from which Cor. I run	
	N. $89^{\circ} 24'$ W. on true line bet. Secs. 17 & 20	
39.96	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits & deposited 1 pint of charcoal, as per instructions.	
49.40	Umatilla, 150 lks. wide, runs, N., N.E.	
79.92	The cor. to Secs. 17, 18, 19 & 24	
	Soil; 3rd rate. Land; rolling.	
	Land; rolling.	