

Subdivisional Lines of T. 4 N., R. 28 E., W.M.

Chains		Feet
	W. on random line bet. Secs. 18 & 19	
40.00	Set post for temp. $\frac{1}{4}$ Sec. cor.	
76.67	Intersect W. Bdy. of tp., 50 lks. S. of the Cor. to Secs. 18, 19, 13 & 24, from which Cor. I run	
	S. $89^{\circ} 38'$ E. on true line bet. Sec. 18 & 19	
36.67	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits and deposited 1 pint of charcoal, as per instructions.	
76.67	The Cor. to Secs. 17, 18, 19 & 24	
	Soil; sandy, 3rd rate Land; level.	
<hr/>		
	N. bet. Secs. 17 & 18	
40.00	Set post for $\frac{1}{4}$ Sec. Cor. in mound with trench and pits and deposited 1 pint of charcoal, as per instructions.	
80.00	Set post for Cor. to Secs. 7, 8, 17 & 18, in mound with trench and pits and deposited 1 pint of charcoal, as per instructions.	
	Soil; 3rd rate, sandy. Land; rolling	
<hr/>		
	E. on random line bet. Secs. 8 & 17	
	Var. 20° E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.55	Intersect N. and S. line, at the Cor. to Secs. 8, 9, 16 & 17, from which Cor. I run	
	W. on true line bet. Secs. 8 & 17.	
3.60	Umatilla, 1.75 lks. wide, runs. N.E.	
40.27 $\frac{1}{2}$	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits and deposited 1 pint of charcoal as per instructions.	
80.55	The Cor. to Secs. 7, 8, 17 & 18	
	Soil; 3rd rate. Land; level	
<hr/>		
	W. on random line bet. Secs. 7 & 18	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
76.56	Intersect W. Bdy. of Tp., 47 lks. S. of Cor. to Secs. 12, 13, 7 & 18, from which Cor. I run	
	S. $89^{\circ} 39'$ E. bet. Secs. 7 & 18	