

Subdivisional Lines of T. 4 N., R. 28 E., W.M.

Chains		Feet
36.56	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits and deposited 1 pint of charcoal, as per instructions.	
76.56	The Cor. to Secs. 7, 8, 17 & 18 Soil; 2nd and 3rd rate. Land; level	
N. bet. Secs. 7 & 8		Oct. 26, 1860.
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits and deposited 1 pint of charcoal as per instructions.	
80.00	Set post for Cor. to Secs. 5, 6, 7 & 8, in mound with trench & pits, and deposited 1 pint charcoal as per instructions.	
E. on random line bet. Secs. 5 & 8.		Var. 20° E.
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.37	Intersect N. and S. line, 65 lks. N. of the Cor. to Secs. 4, 5, 8 & 9, from which Cor. I run N. 89° 32' W. on true line bet. Secs. 5 & 8	
40.18 $\frac{1}{2}$	Set post for $\frac{1}{4}$ Sec. Cor. in mound with trench and pits and deposited 1 pint of charcoal as per instructions.	
80.37	The Cor. to Secs. 5, 6, 7 & 8 Soil; 3rd rate. Land; level	
W. on random line bet. Secs. 6 & 7		
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
76.24	Intersect W. Bdy. of Tp., 62 lks. S. of the Cor. to Secs. 1, 12, 6 & 7, from which Cor. I run S. 89° 32' E., on true line bet. Secs. 6 & 7	
36.24	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits and deposited 1 pint of charcoal, as per instructions.	
76.24	The Cor. to Secs. 5, 6, 7, 8. Soil; 3rd rate. Land; rolling	