

Subdivisional Lines of T. 4 N., R. 29 E., W.M.

Chains		Feet
	N. bet. Secs. 2 & 3	
		Var. 20°30' E.
40.00	Set $\frac{1}{4}$ Sec. post in mound with charred stake as per instructions.	
70.00	Afore named dry branch or run, 20 lks. wide, runs W.	
80.10	Intersect Standard Parallel, 8.49 Chs. W. of Cor. to Secs. 34 & 35, T. 5 N., R. 29 E.	
<hr/>		
	N. bet. Secs. 33 & 34	
		Var. 20° 30' E.
22.00	Bottom of slope	
40.00	Set $\frac{1}{4}$ Sec. Cor. post in mound with charred stake as per instructions.	
80.00	Set post in mound with charred stake as per instructions. Cor. to Secs. 27, 28, 33 & 34.	
<hr/>		
	E. on random bet. Secs. 27 & 34	
		Var. 20°30' E.
40.00	Set temp. $\frac{1}{4}$ Sec. post	
79.96	Intersect N. & S. line, 11 lks. S. of Sec. Cor. S. 89° 55' W. on true line bet. Secs. 27 & 34	
39.98	Set $\frac{1}{4}$ Sec Cor. post in mound with charred stake as per instructions.	
79.96	To Cor. of Secs. 27, 28, 33 & 34 Surface nearly flat Soil; clay & sandy, best yet run by me.	
<hr/>		
	N. bet. Secs. 27 & 28	
		Var. 20°30' E.
40.00	Set $\frac{1}{4}$ Sec. cor. post in mound with charred stake as per instructions.	
60.00	Commence to ascend	
67.00	Top of table	
80.00	Set post in mound with charred stake as per instructions. Cor. to Secs. 21, 22, 27 & 28	