

Subdivisional Lines of T. 4 N., R. 29 E., W.M.

Chains		feet
	instructions.	
80.00	Set post in mound with charred stake as per instructions. Cor. to Secs. 9, 10, 15 & 16 Soil; sandy Surface; undulating, productions, sage, cactus, yarrow, sun flower, bunch grass.	
	E. on random bet. Secs. 10 & 15. Var. 21° E.	
40.00	Set temp. $\frac{1}{4}$ Sec. post	
80.02	Intersect N. & S. line, 45 lks. N. of Sec. Cor. N. 89° 41' W. on true line bet. Secs. 10 & 15. Commence ascending	
40.01	Set $\frac{1}{4}$ Sec. Cor. post in mound with charred stake as per instructions	
80.02	To Cor. of Secs. 9, 10, 15 & 16 Soil; surface etc. as before.	
	N. bet. Secs. 9 & 10	
40.00	Set $\frac{1}{4}$ Sec. Cor. post in mound with charred stake as per instructions.	
80.00	Set post cor. to Secs. 3, 4, 9 & 10, with charred stake in mound as per instructions. Soil; sandy, surface undulating with sage, bunch grass, etc.	
	E. on random bet. Secs. 3 & 10 Var. 19° 15' E.	
40.00	Set temp. $\frac{1}{4}$ Sec. post	
80.22	Intersect N. & S. line, 26 lks. N. of Sec. Cor. N. 89° 49' W. on true line bet. Secs. 3 & 10	
40.11	Set $\frac{1}{4}$ Sec. post in mound with charred stake as per instructions.	
80.22	To Cor. of Secs. 3, 4, 9 & 10 Soil: & surface as before.	