

Subdivisional Lines of T. 4 N., R. 29 E., W.M.

Chains		Feet
	N. bet. Secs. 3 & 4	
		Var. 19°15' E.
40.00	Set $\frac{1}{4}$ Sec. post in mound with charred stake as per instruction	
47.00	Top of rise	
	Table Rock, brs. S. 84° W.	
55.00	Foot of table	
72.25	Dry run, 28 lks. wide, runs W.	
76.00	Top of bluff	
80.00	Intersect Standard Parallel, 7.80 chs. W. of Cor. to Secs. 33 & 34. T. 5 N., R. 29 E.	
	<hr/>	
	N. bet. Secs. 32 & 33	
		Var.
11.00	Foot of rise	
40.00	Set $\frac{1}{4}$ Sec. post in mound with charred stake as per instructions.	
60.00	Commence ascending, table land	
80.00	Set post cor. to Secs. 28, 29, 32 & 33, with charred stake in mound as per instructions.	
	<hr/>	
	E. on random bet. Secs. 28 & 33	
		Var. 20°20' E.
40.00	Set temp. $\frac{1}{4}$ Sec. post	
78.83	Intersect N. & S. line, 85 lks. S. of Sec. Cor. S, 89° 24' W. on true line	
39.41 $\frac{1}{2}$	Set $\frac{1}{4}$ Sec. Cor. in mound with charred stake as per instructions.	
40.83	Walla Walla trail, N. & S.	
68.00	Foot of table or rise	
78.83	To Cor. of Secs. 28, 29, 32 & 33.	
	<hr/>	
	Re-run the S.Bdy. of Sec. 33, and found it to br. S. 89° 30' W., 78.85 Chs. long.	
	<hr/>	