

Subdivisional Lines of T. 4 N., 29 E., W.M.

Chains		Feet
	E. on random bet. Secs. 5 & 8 Var. 20° 30' E.	
40.00	Set temp. $\frac{1}{4}$ Sec. post	
80.14	Intersect N. & S. line, 32 lks. S. of Cor. to Secs. 4, 5, 8, 9 S. 89° 46' W. on true line bet. Secs. 5 & 8	
40.07	Set $\frac{1}{4}$ Sec. Cor. post in mound with charred stake as per instructions.	
80.14	To Cor. of Secs. 5, 6, 7 & 8 Soil; sandy Surface; slightly undulating, with sage, yarrow, bunch grass, etc.	
	W. on random bet. Secs. 6 & 7 Var. 20° 30' E.	
40.00	Set temp. $\frac{1}{4}$ Sec. post	
88.10	Intersect W. Bdy. of the T., 60 lks. N. of the Sec. Cor. N, 89° 32' E. on True line bet. Secs. 6 & 7	
41.10	Commence to ascend	
48.10	Set $\frac{1}{4}$ Sec. post in mound with charred stake, as per instructions.	
88.10	To Cor. of Secs. 5, 6, 7 & 8	
	N. bet. Secs. 5 & 6 Var. 20° 30' E.	
37.00	Foot of table land	
40.00	Set $\frac{1}{4}$ Sec. post in mound with charred stake as per instructions.	
82.58	Intersect the Standard Parallel, 6.56 Chs. W. of Cor. to Secs. 31 & 32, T. 5 N., R. 29 E. Var. 20° 30' E.	
General Description		
of T. 4 N., R. 29 E., W.M. With the exception of a few acres of land in the SW. Cor.		