

Subdivisional Lines of T. 4 N., R. 30 E., W.M.

Chains		Feet
80.00	Set charred stake, with mound, trench & pits as per instructions, for Cor. to Secs. 21, 22, 27 & 28	
	Var. 19° 36' E.	
	Soil; 2nd rate.	
	E. on random bet. Secs. 22 & 27	
40.00	Set temp. $\frac{1}{4}$ Sec. post	
79.76	Intersect Sec. line, 40 lks. S. of Cor. to Secs. 22, 23, 26 & 27	
	S. 89° 42' W. on true line bet. Secs. 22 & 27	
39.88	Set charred stake, with mound, trench & pits as per instructions, for $\frac{1}{4}$ Sec. Cor.	
79.76	Cor. to Secs. 21, 22, 27 & 28	
	Soil; 2nd rate.	
	September 10	
	N. on line bet. Secs. 21 & 22	
40.00	Set charred stake, with mound, trench and pits as per instructions, for $\frac{1}{4}$ Sec. Cor.	
80.00	Set charred stake, with mound, trench & pits as per instructions, for Cor. to Secs. 15, 16, 21 & 22	
	Var. 19° 45' E.	
	Soil; 2nd rate.	
	E. on random bet. Secs. 15 & 22	
40.00	Set temp. $\frac{1}{4}$ Sec. post	
80.16	Intersect Sec. line, 10 lks. S. of Cor. secs. 14, 15, 22 & 23	
	S. 89° 56' W. on true line bet. Secs. 15 & 22	
27.00	Ravine, N. 70° W.	
40.08	Set charred stake, with mound, trench and pits as per instructions, for $\frac{1}{4}$ Sec. Cor.	
80.16	Cor. to Secs. 15, 16, 21 & 22	
	Land; broken & sandy	
	Soil; 3rd rate.	