

Subdivisional Lines of T. 4 N., R. 30 E., W.M.

Chains		Feet
	Soil; 2nd rate.	
	Closing Cor. being in sight, run N. on true line bet. Secs. 3 & 4	
40.00	Set charred stake with mound, trench and pits as per instructions, for $\frac{1}{4}$ Sec. Cor.	
74.98	Intersect Standard Parallel at post cor. to Secs. 33 & 34 T. 5 N., R. 30 & Cor. to Secs. 3 & 4, T 4 N R. 30 E. Same as last mile.	
	September 10th	
	N. on line bet. Secs. 32 & 33	
	Var. 20° 09' E.	
40.00	Set charred stake, with mound, trench and pits as per instructions, for $\frac{1}{4}$ Sec. Cor.	
80.00	Set charred stake, with mound, trench and pits as per instructions, for Cor. to Secs. 28, 29, 32 & 33	
	Var. 20° 09' E.	
	Soil; good	
	Land; mostly level	
	E. on random bet. Secs. 28 & 33	
40.00	Set temp. $\frac{1}{4}$ Sec. post	
80.00	Intersect Sec. line, 35 lks. S. of Cor. to Secs. 27, 28, 33 & 34	
	S. 89° 45' W. on true line bet. Secs. 28 & 33	
40.00	Set charred stake, with mound, trench and pits as per instructions, for $\frac{1}{4}$ Sec. Cor.	
80.00	Cor. to Secs. 28, 29, 32 & 33	
	Soil; 2nd rate.	
	N. on line bet. Secs. 28 & 29	
40.00	Set charred stake, with mound, trench and pits as per instructions, for $\frac{1}{4}$ Sec. Cor.	
80.00	Set charred stake, with mound trench and pits as per instructions, for Cor. to Secs. 20, 21, 28 & 29.	