

Subdivisional Lines of T. 4 N., R. 30 E., W.M.

Chains		Feet
	Var. 20° 15' E.	
	Soil; 2nd rate.	
	<hr/>	
	E. on random bet. Secs. 21 & 28	
40.00	Set temp. $\frac{1}{4}$ Sec. post	
79.55	Intersect Sec. line, 50 lks. S. of Cor. to Secs. 21, 22, 27, 28	
	S. 89° 39' W. on true line bet. Secs. 21 & 28	
39.77	Set charred stake with mound trench and pits as per in- structions, for $\frac{1}{4}$ Sec. Cor.	
79.55	Cor. to Secs. 20, 21, 28 & 29	
	Soil; 2nd rate.	
	<hr/>	
	N. on line bet. Secs. 20 & 21	
40.00	Set charred stake, with mound, trench and pits as per in- structions, for $\frac{1}{4}$ Sec. Cor.	
63.00	Indian Trail & Ravine, N. 80° W.	
30.00	Set charred stake, with mound, trench & pits as per in- structions for Cor. to Secs. 16, 17, 20 & 21	
	Var. 20° 15' E.	
	Soil; 2nd rate.	
	Some sand.	
	<hr/>	
	E. on random bet. Secs. 16 & 21	
40.00	Set temp. $\frac{1}{4}$ Sec. post	
80.25	Intersect Sec. line, 20 lks. N. of Cor. to Secs. 15, 16, 21 & 22	
	N. 89° 51' W. on true line bet. Secs. 16 & 21	
12.00	Indian trail, S. 75° W. and middle of Ravine, S. 75° W.	
40.12	Set charred stake with mound, trench and pits as per in- structions, for $\frac{1}{4}$ Sec. Cor.	
80.25	Cor. to Secs. 16, 17, 20 & 21	
	Soil; 3rd rate.	
	<hr/>	
	N. on line bet. Secs. 16 & 17	